

FOR NOTES & FRAME PREP SEE SHEET 2

DOOR SPECIFICATION

Door Thickness: 1-3/4"
(45mm) Min.


Door Construction: Wood or composite door with fire or panic rating as required. Door may require metal channel edge which may alter backset dimensions. Consult door manufacturers listings.

Exit Device Ratings:

6160-LBR, 6165-LBR,
7160-LBR, 7165-LBR,
Panic Exit Door up to 4' x 8'

6160F90-LBR, 7160F90-LBR,
90 Minutes rated Fire Exit
Door up to 4' x 8'

6160-LBR-10, 6165-LBR-10.,
7-LBR-10, 160 7165-LBR-10,
Panic Exit Door up to 4' x 10'



RESPONSIBILITY

DOOR AND FRAME MANUFACTURERS ARE RESPONSIBLE FOR PROVIDING ADEQUATE CONSTRUCTION OR REINFORCEMENTS FOR PROPER INSTALLATION OF HARDWARE SHOWN. ALL ARCHITECTURAL BUILDERS HARDWARE MUST BE INSTALLED ON PROPERLY REINFORCED DOORS AND FRAMES, REGARDLESS OF TYPE, MATERIAL, OR METHOD OF CONSTRUCTION.

6160(F90)LBR, 7160(F90)LBR, 6165LBR(-10) & 7165LBR(-10)

Concealed Vertical Rod Exit Devices


Application for Wood Door & Metal Frame Less Bottom Rod;
761 Top Strike

Contact us for support at 1-855-557-5078.

ASSA ABLOY

SUPERSEDES	12/16	DO NOT SCALE DRAWING	
TEMPLATE NUMBER	7470-1065	SHEET	1 of 2
		DATE	12-23

761 Top Strike Preparation (See Note 6)



NOTES:

1. Do not scale drawing.
2. Dimensions are in inches (mm).
3. Preparation is typical for both hands.
4. Minimum door stile width: 4-1/2 (114).
5. Prepare mounting holes when installing the device.
6. Drawing shows elevation (frame bisected on strikecenter), bottom view looking up and side view.
7. Provide adequate structural support to maintain door integrity after device installation with power tools, door use, or abuse.
8. Door located in frame for door silencers. If not used, compensate this dimension to seat the door against the stop without rattle.
9. Device mount to hinge stile (not shown) requires hole location and preparation during device installation. Door structural requirements are similar for both stiles.
10. For outside trim preparation see appropriate trim template.
11. For electrical devices (suffixes "-B", "-G", "-O", "-P", "-S") also see template 7477-0001.
12. For labeled door pairs only. Reinforce door as needed for heat activated interlocking bolt. See template 7470-1700.
13. Door structure as required for heat activated interlocking bolt. 1-1/2 square 16 ga. plate recommended.

RESPONSIBILITY

DOOR AND FRAME MANUFACTURERS ARE RESPONSIBLE FOR PROVIDING ADEQUATE CONSTRUCTION OR REINFORCEMENTS FOR PROPER INSTALLATION OF HARDWARE SHOWN. ALL ARCHITECTURAL BUILDERS HARDWARE MUST BE INSTALLED ON PROPERLY REINFORCED DOORS AND FRAMES, REGARDLESS OF TYPE, MATERIAL, OR METHOD OF CONSTRUCTION.

**6160(F90)LBR, 7160(F90)LBR, 6165LBR(-10)
& 7165LBR(-10)**

Concealed Vertical Rod Exit Devices
Application for Wood Door & Metal Frame Less Bottom Rod;
761 Top Strike

Contact us for support at 1-855-557-5078.

ASSA ABLOY

SUPERSEDES	12/16	DO NOT SCALE DRAWING	
TEMPLATE NUMBER	7470-1065	SHEET	2 of 2
		DATE	12-23